GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 31st July 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M., on 29th August 1931, for constructing (1) 3 blocks of Operators' Quarters, (2) 5 blocks of Cooly Quarters at Mysore.

1. The tenders will be opened in public at 2 P.M., on the 29th August 1931. The works should be completed within six months and the monthly progress should not be less than Rs. 2,000 and Rs. 2,500 for item (1) and (2) respectively.

2. The quantities given are approximate, and the plans, detailed estimates and conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or in Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Staff Quarters at Mysore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of the Notification of the acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryots' specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department :—

Statement showing the approximate quantities of work for constructing one block of Cooly Quarters with a block of Latrine at Mysore.

Sl. No.	Details of work	Unit	Quantity	
			Cooly quarters	Latrine
1	Earthwork excavation and filling in basement	C.yd.	37	11
2a	Stone jelly in lime mortar concrete foundation	C.ft.	317	
b	Coursed rubble stone masonry in mortar foundation and basement	"	900	360
c	Burnt brick in clay, superstructure	"	2,070	
d	Burnt brick in mortar do	"	352	476
e	Stone slabs 4" thick roughly dressed and fixed in mortar	S.ft.	156	40
f	Stone pillars 4" thick roughly dressed including paly cutting and fixing in position	"	26	
g	Plain cornice 6" projection built of brick in mortar and chunam plastered complete	R.ft.	75	
h	Chunam plastering two coats	Sqr.	52·16	10·6
i	Mortar pointing with lining	"	1·00	0·75

Sl. No.	Details of work	Unit	Quantities	
			Cooly quarters	Latrines
2j	White nd colour washing two coats	Sqr.	53·16	10·81
k	Binding wall 1½" x ½" built of brick in mortar and chunam-plastered.	R.ft.	74	..
l	Chunam borders 6" x 3" over verandah roof	,,	30	..
m	Burnt brick in mortar coping 9" thick with plastering, etc., complete.	,,	..	116
3a	Flooring on 3" concrete and finished with chunam plaster on top.	Sqr.	8·30	..
b	Flooring on 3" concrete bed with cement plastering on top ½" thick complete.	,,	..	1·30
c	Cement plastering ½" thick	,,	..	2·90
d	Tarring two coats	,,	11·81	2 90
4a	Roofing with 1st Class Mangalore tiles on teak rafters complete (rate for Yelahanka tiles roofing may also be quoted.	,,	..	..
b	Ridge tiles set in mortar and cement pointed	R.ft.	23	..
c	Ventilating tiles	Each	16	..
d	Honney wood work with wood oiling 2 coats	C.ft.	41·50	..
e	Honney wood battened doors shutters 1½" thick with fittings, etc., complete frames 4" x 3½" vide drawing No. M—147.	S.ft.	78	..
f	Honney wood battened windows shutters 1" thick with fittings, etc., complete frames 3½" x 3" vide drawing No. M—147.	,,	70	..
g	Honney wood ventilators with wire gauze shutters fixed complete frames 3" x 3" vide drawing No. M—147.	,,	24	..
h	Chocolate pointing 2 coats	Sqr.	3·55	..
i	Fixing iron clamps to doors and windows	Each	24	..
5	Constructing sinks with drain pipes complete	,,	4	..
6	Stone mortar and pestle including fixing charges	,,	4	..
7	Fixing outlets from the latrines to the drain	,,	5	..

Statement showing the approximate quantities of work for constructing one unit of Operator's Quarters for accommodating two families and one block of latrine at Mysore.

		Unit	Operator's quarters	Latrine
1	Earthwork excavation and filling in basement	C.yd.	161	4
2a	Stone jelley in lime mortar concrete foundation	C.ft.	1,577	..
b	Stone in clay foundation and basement	,,	1,056	130
c	Burnt brick in clay superstructure	,,	2,551	..
d	Stone slabs 6" thick roughly dressed and set in mortar	S.ft.	237	..
e	Stone slabs 4" thick set in lime	,,	24	..
f	Chunam plastering two coats	Sqr.	56·36	4·91
g	Chunam pointing with thread lines	,,	2·10	0·76
h	White and colour washing 2 coats	,,	58·46	5·47
i	Binding wall 1 1/8" x 9" brick in mortar and chunam plastered.	R.ft.	44	..
j	Plain cornice 6" projection complete	,,	44	..
k	Constructing sinks complete	Each	2	..
l	Providing stone mortar and pestle	,,	2	..
3a	Flooring with 1st Class Mangalore tiles on 3" concrete including cement pointing complete.	Sqr.	4·25	..
3b	Cuddapah slab flooring on 3" concrete, including cement pointing complete.	,,	4·50	..
4a	Roofing with 1st Class Mangalore tiles on teak wood rafters 2" x 1" (rate for Yelahanka tile roofing may also be quoted.	,,	19·72	..
b	Ridge tiles set in mortar and cement pointed	R.ft.	41	..
c	Terrace roofing with Cuddapah slabs 1½" thick with 3" brick concrete 2 layers of flat tiles and surface plastered and ceiling pointed with cement and white washed, etc.	Sqr.	3·20	..
d	Burnt brick in mortar cornice projection 9" complete	R.ft.	83	..
e	Burnt brick in mortar parapet wall 9" thick as per design.	C.ft.	59	..
5a	Mattywood wrought and put up with 2 coats of wood oiling.	,,	34·17	..
b	Steel girders fixed complete (Dorman Long make) (rate for girders (Tata make) may also be quoted.	Each	19·13	..
c	Doors with teakwood frames and honneywood battened shutters 1" thick with fittings complete.	Sqr.	279·5	..
d	Windows with teakwood frames and honneywood battened shutters 1" thick with iron bars 5/8" diameter, etc.	,,	116	..
e	Honneywood planks 1½" thick for the shelves with teakwood pegs fixed complete.	,,	48	..
f	Chocolate painting 2 coats	,,	13·28	..
g	Expanded metal 3" x 1½" by ½" with teakwood frames work fixed complete.	S.ft.	113	..
6	Rain water down pipe 3" diameter fixed complete	R.ft.	20	..
7	Brick in mortar pillar 1.4" square with base and capital complete with chunam plaster 7'—7" high.	Each	1	..
8	Burnt brick in mortar Super structure	C.ft.		196
9	Cement plastering ½" thick	Sqr.		0·79
10	Tar washing 2 coats	,,		0·68
11	Flooring with 3" concrete and cement plaster ½" thick	,,		0·38
12	Providing galvanized iron sheet tubs 12" x 8" complete with tarring.	Each		No. 6

C. M. CARIAPA,
Chief Electrical Engineer.